

**QUOTE FOR LABOUR RATE CONTRACT FOR THE WORKS OF REPAIR & MAINTENANCE IN RGCA - AQUATIC QUARANTINE FACILITY AT NEELANKARAI, CHENNAI.**

Sl. No.	Item of Work	Quantity	Unit	Rate (in Rs.)	Amount (in Rs.)	Amount (in words)
<b><u>ROOFING WORKS (STRUCTURAL STEEL &amp; ROOF SHEET)</u></b>						
<b>1</b>	<b><u>DISMANTLING AND DEMOLISHING</u></b>					
i	Labour charges for Dismantling steel work in builtup sections in angles, tees, flats and channels including all gusset plates, bolts and nuts, cutting rivets, weldings etc., including dismembered servicable materials stacking etc., complete as per CPWD technical specifications / as specified by the Engineer - In Charge					
a	Tubular Truss / Angle Truss	2,500.00	Kg			
ii	Labour Charges for Dismantling roofing including ridges, hips, valleys and guiers etc., including dismembered servicable materials stacking etc., complete as per CPWD technical specifications / as specified by the Engineer - In Charge					
a	Non Asbestos / FRP	1,350.00	Sq.m			
<b>2</b>	<b><u>FABRICATION WORK</u></b>					
i	Fabrication of Structural steel work riveted, bolted or welded in built up sections, trusses and framed works including cutting, hoisting, fixing in position and applying a priming coat of approved steel anti corrosive primer paint etc., all complete as per CPWD technical specifications / as specified by the Engineer - In Charge					
a	Tubular Truss	850.00	Kg			
b	Angle Truss	20,950.00	Kg			
ii	Repair and refabrication of Structural steel work riveted, bolted or welded in built up sections, trusses and framed works including cutting, hoisting, fixing in position and applying a priming coat of approved steel anti corrosive primer paint etc., all complete as per CPWD technical specifications / as specified by the Engineer - In Charge					
a	Tubular Truss		Kg			
b	Angle Truss	665.00	Kg			
		150.00				
<b>3</b>	<b><u>ROOFING</u></b>					
i	Labour charges for Removal of existing AC Sheets/FRP sheets & laying of new sheets (Non -Asbestos Sheet / FRP Sheet) with all accessories & necessary scaffolding as per CPWD technical specifications / as specified by the Engineer - In Charge	855.00	Sq. M			
ii	Labour charges for laying of Non - Asbestos Cement Sheet/FRP sheets with all accessories & necessary scaffolding as per CPWD technical specifications / as specified by the Engineer - In Charge	1,675.00	Sq. M			
<b>4</b>	<b><u>PAINTING WORKS</u></b>					
i	Labour charges for Scrapping & Cleaning old painted surface with necessaary scaffolding & scrapping materials on galvanised Iron/Mild Steel sections as per CPWD technical specifications / as specified by the Engineer - In Charge	838.00	Sq. M			
ii	Labour charges for Painting with ZINC primer two or more coat on new work of galvanised Iron/Mild Steel Sections as per CPWD technical specifications / as specified by the Engineer - In Charge	988.00	Sq. M			
iii	Labour charges for Painting with synthetic enamel paint two or more coat with one coat of primer to give an even shade on new work of galvanised Iron/Mild Steel Sections. as per CPWD technical specifications / as specified by the Engineer - In Charge	988.00	Sq. M			

iv	Labour charges for Painting with Epoxy / MRF paint two or more coat with one coat of primer to give an even shade on galvanised Iron/Mild Steel Sections. as per CPWD technical specifications / as specified by the Engineer - In Charge	QRO	Sq. M			
v	Labour charges for Scrapping & Cleaning old painted surface with necessaary scaffolding and Painting with synthetic enamal paint for roof truss to give an even shade as per CPWD technical specifications / as specified by the Engineer - In Charge.	QRO	Sq. M			
vi	Labour charges for Painting with SIEMENS 8426 paint two or more coat with one coat of primer to give an even shade on PUF wall Panels & galvanised Iron/Mild Steel Sections by machine spraying. as per CPWD technical specifications / as specified by the Engineer - In Charge	859.00	Sq. M			
<b>Note</b> :	The rates furnished by the Contractor should be inclusive of water, power & other machineries required for the works to be carried out at Site. Also the rate shall inclusive of all applicable TAX.					