

**QUOTE FOR THE SUPLY OF MATERIALS FOR THE WORK OF RENOVATION & UPGRADATION
SUFFIENCY PROJECT OF MPEDA AT VALLARPADAM, COCHIN**

Sl. No.	Item of Work	QTY (approx)	Unit	Rate/unit (in Rs.)
<u>CONSTRUCTION RAW MATERIALS</u>				
1	CEMENT (SRC)Sulphur Resistant Cement 43 grade ISI branded)-Approved make.	3600.00	Bags	
2	River Sand	#REF!	Cu.m	
3	Quary/Crusher Dust	1100.00	Cu.m	
4	Available Good Earth brought from outside	3900.00	Cu.m	
5	Available Clay brought from outside	650.00	Cu.m	
6	Red Bricks (1st class / Chamber) Average Compressive strength not less than 50kg/cm2	72000.00	Nos.	
7	Precast Cement concrete Solid Blocks of size 20cmx40cmx20cm(per unit rate)	quantity not estimated	Nos.	
8	Precast Cement concret Hollow Blocks of size 20cmx40cmx20cm (per unit rate)	quantity not estimated	Nos.	
9	Factory made 80 mm thick CC Interlocking Paver blocks of M-40 Grade made by blockmaking machine with strong vibratory compaction of approved size, design shape and colour.	2400.00	Sq.m	
10	Factory made 63/65mm thick CC Interlocking Paver blocks of M-30 Grade made by blockmaking machine with strong vibratory compaction of approved size, design shape and colour.		Sq.m	
11	6mm size stone aggregate(per unit rate)	quantity not estimated	Cu.m	
12	10/12 mm size stone aggregate(per unit rate)	quantity not estimated	Cu.m	
13	20 mm size stone aggregate	200.00	Cu.m	
14	40 mm size stone aggregate	650.00	Cu.m	
15	60 / 80 mm size boulders stone aggregate(per unit rate)		Cu.m	
16	8mm dia CRS Bars (Corrosion Resistant Steel FE 415 Properties, ISI branded) Approved make.			

17	10mm dia CRS Bars (Corrosion Resistant Steel FE 415 Properties, ISI branded)	24500.00	Kg.	
18	12 mm dia CRS Bars (Corrosion Resistant Steel FE 415 Properties, ISI branded)			
19	16mm dia CRS Bars (Corrosion Resistant Steel FE 415 Properties, ISI branded)			
20	Water proofing cement primer	500.00	Lit	
21	Sandex Mat For finishing	400.00	Lit	
22	Zincromate Steel Primer	100.00	Lit	
23	Steel Enamel Finishing	170.00	Lit	
24	Epoxy Primer	180.00	Lit	
25	Epoxy Finishing	250.00	Lit	
26	Aluminium Doors / Windows	#REF!	Sq.m	
	False Ceiling -GYPSUM		Sq.m	
27	Non Asbestos high impact polypropylene reinforced cement 6mm thick corrugated sheet (as per IS :14871) roofing up to any pitch of size 3Mx1M	700.00	Nos.	
28	HDPE LINNING 500 μ with max. 7.00 M width roll	13000.00	Sq.m	
29	Domestic Fresh water (rate/12ton)	12.00	ton	
Note:	<p>The rates furnished by the Contractor / supplier should be inclusive of all supporting charges such as unloading and transportation to MPEDA site at Vallarpadam etc. The quoted rate should be applicable from 2018. Quotations from authorized dealers/ registered suppliers/ agencies / contractors only will be accepted. Quotations addressed to The Project Director, Rajiv Gandhi Centre for Aquaculture (RGCA), MPEDA, (Ministry of Commerce & Industry, Govt. of India), Panampilly Nagar, Cochin-682036 should be submitted before 11.00am on 10/08/2017. Quotations can be submitted either by hand or through post/ courier in the mentioned address. Quotations submitted through e-mail will not be accepted. RGCA will not be responsible for postal delay in connection with the submission of quotations.</p>			

<u>OF SELF</u>					
Remarks					
					0
				e	

