

**QUOTE FOR LABOUR RATE CONTRACT WORKS FOR THE WORK OF RENOVATION & UPGRADATION
OF SELF SUFFICIENCY PROJECT OF MPEDA IN VALLARPADAM AT COCHIN**

Sl. No.	Item of Work	Unit	Rate (in Rs.)	Remarks
<u>ROOFING WORKS (STRUCTURAL STEEL & ROOF SHEET)</u>				
1	Painting with ZINC primer two or more coat on galvanised Iron/Mild Steel Sections as per CPWD technical specifications / as specified by the Engineer - In Charge	Sq. M		
2	Painting with synthetic enamel paint two or coat to give an even shade on galvanised Iron/Mild Steel Sections. as per CPWD technical specifications / as specified by the Engineer - In Charge	Sq. M		
3	Painting with Epoxy / MRF paint two or coat to give an even shade on galvanised Iron/Mild Steel Sections. as per CPWD technical specifications / as specified by the Engineer - In Charge	Sq. M		
4	<u>PAINTING OLD WORKS</u>			
i	Scrapping & Cleaning old painted surface with necessaary scaffolding and Painting with primer on galvanised Iron/Mild Steel sections as per CPWD technical specifications / as specified by the Engineer - In Charge	Sq. M		
ii	Scrapping & Cleaning old painted surface with necessaary scaffolding and Painting with synthetic enamel paint for roof truss to give an even shade as per CPWD technical specifications / as specified by the Engineer - In Charge.	Sq. M		
5	<u>FABRICATION WORK</u>			
a	Fabrication of Structural steel work riveted, bolted or welded in built up sections, trusses and framed works including cutting, hoisting, fixing in position and applying a priming coat of approved steel anti corrosive primer paint etc., all complete as per CPWD technical specifications / as specified by the Engineer - In Charge			
i	Tubular Truss	Kg		

ii	Angle Truss	Kg		
b	Repair and refabrication of Structural steel work riveted, bolted or welded in built up sections, trusses and framed works including cutting, hoisting, fixing in position and applying a priming coat of approved steel anti corrosive primer paint etc., all complete as per CPWD technical specifications / as specified by the Engineer - In Charge			
i	Tubular Truss	Kg		
ii	Angle Truss	Kg		
6	<u>ROOFING</u>			
a	Removal of existing AC Sheets/FRP sheets & laying of new sheets with all accessories & necessary scaffolding as per CPWD technical specifications / as specified by the Engineer - In Charge	Sq. M		
b	laying of Non - Asbestos Cement Sheet/FRP sheets with all accessories & necessary scaffolding as per CPWD technical specifications / as specified by the Engineer - In Charge	Sq. M		
Note:	The rates furnished by the Contractor should be inclusive of water, power & other machineries required for the works to be carried out at Site.			